

■ PA UCC Architectural Code Audit Report

■ Architectural Building Code Compliance Audit Report

Drawing File: `sample\_plan\_A101.pdf`

Governing Code: Pennsylvania Uniform Construction Code (34 Pa. Code Ch. 401-405 / Act 45) - 2021 I-Codes & PA Statutory Amendments

■ Audit Summary Table

| Element | Extracted Value | Required Code | Status | Citation |

| :--- | :--- | :--- | :--- | :--- |

| MAIN EXIT CORRIDOR A | 38.0 inches | ≥ 44.0 inches | **FAIL (VIOLATION)** | 2021 IBC § 1020.3 / PA UCC |

| DOOR 101 CLEAR WIDTH | 32.0 inches | ≥ 32.0 inches | **PASS** | 2021 IBC § 1010.1.1 / PA UCC |

| OFFICE 101 CEILING HEIGHT | 96.0 inches (8'-0") | ≥ 90.0 inches | **PASS** | 2021 IBC § 1207.2 / PA UCC |

| EGRESS TRAVEL DISTANCE | 42.5 feet | ≤ 75.0 feet | **PASS** | 2021 IBC § 1006.2.1 / PA UCC |

| RESTROOM WHEELCHAIR TURN CLEARANCE | 60.0 inches | ≥ 60.0 inches | **PASS** | 2009 ICC A117.1 § 604 / 2018 IBC § 1109.2 (PA Court Mandate) |

| STAIR RISER HEIGHT (STAIR A) | 6.75 inches | ≤ 7.0 inches | **PASS** | 2021 IBC § 1011.5.2 / PA UCC |

| STAIR TREAD DEPTH (STAIR A) | 11.5 inches | ≥ 11.0 inches | **PASS** | 2021 IBC § 1011.5.3 / PA UCC |

| STAIR HANDRAIL HEIGHT | 36.0 inches | 34" - 38" | **PASS** | 2021 IBC § 1014.2 / PA UCC |

| OFFICE OCCUPANT LOAD FACTOR | 150 sq ft/person | 150 sq ft/person | **PASS** | 2021 IBC Table 1004.5 / PA UCC |

| ELEC PANEL 'E1' WORKING CLEARANCE | 36.0 inches depth | ≥ 36.0 inches | **PASS** | NEC 110.26(A)(1) / PA UCC |

| ELEC ROOM DEDICATED HEADROOM | 84.0 inches (7'-0") | ≥ 78.0 inches | **PASS** | NEC 110.26(E)(1)(a) / PA UCC |

| RESTROOM RECEPTACLES GFCI | GFCI Specification Identified | REQUIRED | **PASS** | NEC 210.8(B) / PA UCC |

| FIRE EXTINGUISHER TRAVEL DISTANCE | 50.0 feet | ≤ 75.0 feet | **PASS** | 2021 IFC § 906.1 / PA UCC |

| EMERGENCY EGRESS ILLUMINATION | 1.2 foot-candles | ≥ 1.0 fc | **PASS** | 2021 IBC § 1008.3.5 / PA UCC |

| MANUAL PULL STATION EXIT DISTANCE | 3.5 feet from EXIT 1 | <= 5.0 feet | **PASS** | 2021 IBC § 907.4.2 / PA UCC |

| RESTROOM WATER CLOSET COUNT | 3 Fixtures (25 Occupants) | 1 per 50 occupants | **PASS** | 2021 IPC Table 403.1 / PA UCC |

| PUBLIC LAVATORY HOT WATER TEMP | 105.0 °F | <= 110.0 °F | **PASS** | 2021 IPC § 419.5 / PA UCC |

| OFFICE OUTDOOR VENTILATION RATE | 7.5 CFM / person | >= 5.0 CFM / person | **PASS** | 2021 IMC Table 403.3.1.1 / PA UCC |

| ACCESSIBLE ENTRANCE RAMP SLOPE | 1:14 (7.14% slope) | <= 1:12 (8.33%) | **PASS** | 2021 IBC § 1012.2 / PA UCC |

| RAMP LANDING CLEAR LENGTH | 60.0 inches | >= 60.0 inches | **PASS** | 2021 IBC § 1012.6.3 / PA UCC |

| MEZZANINE GUARDRAIL HEIGHT | 42.0 inches | >= 42.0 inches | **PASS** | 2021 IBC § 1015.3 / PA UCC |

| GUARDRAIL BALUSTER SPACING | 3.75 inches clear opening | < 4.0 inches sphere | **PASS** | 2021 IBC § 1015.4 / PA UCC |

| FIRE SPRINKLER DEFLECTOR CLEARANCE | 24.0 inches clear below head | >= 18.0 inches | **PASS** | 2021 NFPA 13 § 10.2.8.1 / PA UCC |

| CORRIDOR ENCLOSURE FIRE RATING | 1-Hour Fire Resistance Assembly | 1.0 Hour Assembly | **PASS** | 2021 IBC Table 1020.2 / PA UCC |

| ADA RESTROOM GRAB BAR HEIGHT | 34.0 inches above finished floor | 33 - 36 inches | **PASS** | 2009 ICC A117.1 § 604.5 / PA Court Mandate |

| COMMERCIAL KITCHEN TYPE I HOOD | Type I Exhaust Hood Specified | REQUIRED | **PASS** | 2021 IMC § 507.2 / PA UCC |

| ENVELOPE CONTINUOUS AIR BARRIER | Continuous Membrane Specified | REQUIRED | **PASS** | 2021 IECC § C402.5.1 / PA UCC |

| WATER MAIN BURIAL FROST DEPTH | 42.0 inches below grade | >= 36.0 inches | **PASS** | 2021 IPC § 305.4.1 / PA UCC |

| EAST WING DEAD-END CORRIDOR | 14.0 feet | <= 20.0 feet | **PASS** | 2021 IBC § 1020.5 / PA UCC |

| EXIT DOOR LATCH OPERATING HEIGHT | 40.0 inches above finished floor | 34 - 48 inches | **PASS** | 2021 IBC § 1010.1.9.2 / PA UCC |

| MAIN ENTRANCE THRESHOLD HEIGHT | 0.375 inches (3/8") | <= 0.5 inches | **PASS** | 2021 IBC § 1010.1.6 / PA UCC |

| ADA PARKING STALL CLEAR WIDTH | 96.0 inches (8'-0") | >= 96.0 inches | **PASS** | 2009 ICC A117.1 § 502 / PA Court Mandate |

| SOUTH EXTERIOR WALL FIRE RATING | 1-Hour Fire Resistance Assembly | 1.0 Hour Assembly | **PASS** | 2021 IBC Table 602 / PA UCC |

| ROOF ASSEMBLY CONTINUOUS INSULATION | R-30.0 Continuous Insulation | >= R-30.0 | **PASS** | 2021 IECC Table C402.1.3 / PA UCC |

| EXTERIOR FENESTRATION SHGC | 0.32 SHGC | <= 0.40 | **PASS** | 2021 IECC Table C402.4 / PA UCC |

| MAIN SEWER DRAIN CLEANOUT SPACING | 75.0 feet | <= 100.0 feet | **PASS** | 2021 IPC § 708.1.1 / PA UCC |

| MAIN WATER SERVICE BACKFLOW PREVENTER | RPZ Backflow Assembly Specified | REQUIRED | **PASS** | 2021 IPC § 608.1 / PA UCC |

| CHANGE OF OCCUPANCY SAFETY EVALUATION | Full Code Analysis Sheet Included | REQUIRED | **PASS** | 2021 IEBC § 1001.1 / PA UCC |

| ASSEMBLY ROOM EXIT DOOR COUNT | 2 Exit Doors Provided | >= 2 Exits | **PASS** | 2021 IBC § 1006.3.3 / PA UCC |

| EXIT SEPARATION DISTANCE FRACTION | 0.45 Diagonal Distance | >= 0.33 Fraction | **PASS** | 2021 IBC § 1007.1.1 / PA UCC |

| EGRESS DOOR SWING DIRECTION | Swings in Direction of Exit Travel | REQUIRED | **PASS** | 2021 IBC § 1010.1.2.1 / PA UCC |

| ASSEMBLY EXIT PANIC HARDWARE | UL Listed Panic Hardware Specified | REQUIRED | **PASS** | 2021 IBC § 1010.1.10 / PA UCC |

| STAIR HANDRAIL EXTENSION LENGTH | 12.0 inches top/bottom extension | >= 12.0 inches | **PASS** | 2021 IBC § 1011.11 / PA UCC |

| PRIMARY EXIT SIGN MARKING | Tactile & Illuminated EXIT Signs | REQUIRED | **PASS** | 2021 IBC § 1013.2 / PA UCC |

| EXIT SIGN LETTER HEIGHT | 6.0 inches letter height | >= 6.0 inches | **PASS** | 2021 IBC § 1013.6.1 / PA UCC |

| WORKSTATION AISLE CLEAR WIDTH | 42.0 inches | >= 36.0 inches | **PASS** | 2021 IBC § 1018.1 / PA UCC |

| NATURAL VENTILATION GLAZING AREA | 5.2% of Floor Area | >= 4.0% | **PASS** | 2021 IBC § 1203.1 / PA UCC |

| HABITABLE ROOM ARTIFICIAL LIGHTING | 15.0 foot-candles | >= 10.0 fc | **PASS** | 2021 IBC § 1204.1 / PA UCC |

| OFFICE HABITABLE FLOOR AREA | 120.0 sq ft | >= 70.0 sq ft | **PASS** | 2021 IBC § 1208.1 / PA UCC |

| OFFICE ROOM MIN HORIZONTAL DIMENSION | 10.0 feet width | >= 7.0 feet | **PASS** | 2021 IBC § 1208.2 / PA UCC |

| FOOTING FROST DEPTH PROTECTION | 42.0 inches below grade | >= 42.0 inches | **PASS** | 2021 IBC § 1809.5 / PA UCC |

| MAXIMUM FORWARD REACH HEIGHT | 44.0 inches | <= 48.0 inches | **PASS** | 2009 ICC A117.1 § 308.2 / PA Court Mandate |

| MINIMUM LOW REACH HEIGHT | 18.0 inches | >= 15.0 inches | **PASS** | 2009 ICC A117.1 § 308.3 / PA Court Mandate |

| DOOR PULL SIDE MANEUVERING CLEARANCE | 24.0 inches latch clearance | ≥ 18.0 inches | **PASS** | 2009 ICC A117.1 § 404.2.3 / PA Court Mandate |

| WATER CLOSET CENTERLINE SIDE CLEARANCE | 18.0 inches from side wall | 16 - 18 inches | **PASS** | 2009 ICC A117.1 § 604.2 / PA Court Mandate |

| LAVATORY SINK KNEE CLEARANCE HEIGHT | 29.0 inches clear knee height | ≥ 27.0 inches | **PASS** | 2009 ICC A117.1 § 606.2 / PA Court Mandate |

| ELEC PANEL WORKING SPACE WIDTH | 36.0 inches width | ≥ 30.0 inches | **PASS** | NEC 110.26(A)(2) / PA UCC |

| DWELLING AFCI PROTECTION | AFCI Breakers Specified | REQUIRED | **PASS** | NEC 210.12(B) / PA UCC |

| WALL RECEPTACLE MAX SPACING | 10.0 feet along perimeter | ≤ 12.0 feet | **PASS** | NEC 210.52(A)(1) / PA UCC |

| KITCHEN COUNTER RECEPTACLE SPACING | 36.0 inches | ≤ 48.0 inches | **PASS** | NEC 210.52(C)(1) / PA UCC |

| MAIN BREAKER MAX HANDLE HEIGHT | 67.0 inches | ≤ 79.0 inches | **PASS** | NEC 240.24(A) / PA UCC |

| TAMPER RESISTANT RECEPTACLES | TR Listed Receptacles Specified | REQUIRED | **PASS** | NEC 406.12 / PA UCC |

| FIRE ACCESS ROAD UNRESTRICTED WIDTH | 24.0 feet paved width | ≥ 20.0 feet | **PASS** | 2021 IFC § 503.2.1 / PA UCC |

| FIRE ACCESS ROAD VERTICAL CLEARANCE | 14.0 feet clear height | ≥ 13.5 feet | **PASS** | 2021 IFC § 503.2.2 / PA UCC |

| STREET ADDRESS NUMERAL HEIGHT | 6.0 inches reflect numerals | ≥ 4.0 inches | **PASS** | 2021 IFC § 505.1 / PA UCC |

| FIRE HYDRANT DISTANCE TO BUILDING | 150.0 feet | ≤ 400.0 feet | **PASS** | 2021 IFC § 507.5.1 / PA UCC |

| FIRE ALARM AUDIBLE SIGNAL LEVEL | 20.0 dBA above ambient | ≥ 15.0 dBA | **PASS** | 2021 NFPA 72 § 18.4.1.2 / PA UCC |

| FIRE ALARM STROBE LIGHT HEIGHT | 88.0 inches AFF | 80 - 96 inches | **PASS** | 2021 NFPA 72 § 18.5.5.1 / PA UCC |

| PIPE FOUNDATION WALL PENETRATION SLEEVE | Schedule 40 Sleeve Installed | REQUIRED | **PASS** | 2021 IPC § 305.4 / PA UCC |

| WATER CLOSET SIDE CLEARANCE | 18.0 inches to partition | ≥ 15.0 inches | **PASS** | 2021 IPC § 405.3.1 / PA UCC |

| WATER CLOSET FRONT CLEARANCE | 30.0 inches clear in front | ≥ 21.0 inches | **PASS** | 2021 IPC § 405.3.1 / PA UCC |

| PUBLIC LAVATORY FAUCET FLOW RATE | 0.5 GPM Aerator | ≤ 0.5 GPM | **PASS** | 2021 IPC Table 604.4 / PA UCC |

| COMMERCIAL WATER CLOSET FLUSH RATE | 1.28 GPF Flush Valve | ≤ 1.6 GPF | **PASS** | 2021 IPC Table 604.4 / PA UCC |

| EXHAUST TERMINATION WINDOW CLEARANCE | 10.0 feet distance | ≥ 3.0 feet | **PASS** | 2021 IMC § 501.3.1 / PA UCC |

| FLEXIBLE DUCT MAXIMUM LENGTH | 8.0 feet flex connector | ≤ 14.0 feet | **PASS** | 2021 IMC § 603.6.1.1 / PA UCC |

| 1-HOUR WALL DUCT FIRE DAMPER | Combination Fire/Smoke Damper | REQUIRED | **PASS** | 2021 IMC § 607.5.2 / PA UCC |

| COMMERCIAL THERMOSTAT SETBACK CONTROL | 7-Day Programmable Setback | REQUIRED | **PASS** | 2021 IECC § C403.2.4 / PA UCC |

| OFFICE LIGHTING OCCUPANCY SENSOR | Dual-Tech Occupancy Sensors | REQUIRED | **PASS** | 2021 IECC § C405.2 / PA UCC |

| OFFICE LIGHTING POWER DENSITY (LPD) | 0.52 Watts / sq ft | ≤ 0.64 W/sq ft | **PASS** | 2021 IECC Table C405.3.2(1) / PA UCC |

| ALTERATION MODERN CODE CONFORMANCE | New Framing Conforms to Code | REQUIRED | **PASS** | 2021 IEBC § 702.1 / PA UCC |

| ALTERATION AREA ACCESSIBILITY COMPLIANCE | Accessible Route Maintained | REQUIRED | **PASS** | 2021 IEBC § 705.1 / PA UCC |

| DOOR LATCH RELEASING FORCE | 8.0 lbf operating force | ≤ 15.0 lbf | **PASS** | 2021 NFPA 101 § 7.2.1.4.1 / PA UCC |

| UNLATCHING EGRESS DOOR LOCKS | Single Motion Unlatching | REQUIRED | **PASS** | 2021 NFPA 101 § 7.2.1.5.2 / PA UCC |

| ACCESSIBLE EGRESS STAIRWAY WIDTH | 54.0 inches between rails | ≥ 48.0 inches | **PASS** | 2021 IBC § 1009.3 / PA UCC |

| DOOR LITE SAFETY GLAZING | ANSI Z97.1 Tempered Glass | REQUIRED | **PASS** | 2021 IBC § 2406 / PA UCC |

| CONCEALED WALL FIREBLOCKING | 2x Framing Fireblocking | REQUIRED | **PASS** | 2021 IBC § 718.2 / PA UCC |

| PA RESIDENTIAL SPRINKLER EXEMPTION | No Sprinkler System Required | EXEMPT (Act 1) | **PASS** | 34 Pa. Code § 403.21 / PA Act 1 |

| PA RESIDENTIAL STAIR RISER / TREAD | 8.0 in riser / 9.0 in tread | Max 8.25" / Min 9.0" | **PASS** | PA Act 13 of 2004 / 1992 CABO |

| PA FLOODPLAIN LOWEST FLOOR ELEVATION | 2.0 feet above BFE | $\geq$ BFE + 1.0 ft | **PASS** | 34 Pa. Code § 403.62 / PA UCC |

| PA POOL BARRIER ENCLOSURE HEIGHT | 48.0 inches height | >= 48.0 inches | **PASS** | 34 Pa. Code § 403.26 / PA UCC |

| PA POOL ENCLOSURE GATE LATCH | Self-Closing & Latching Gate | REQUIRED | **PASS** | 34 Pa. Code § 403.26 / PA UCC |

| UNDERGROUND GAS PIPE SLAB PROTECTION | Ventilated Conduit Installed | REQUIRED | **PASS** | 2021 IFGC § 404.2 / PA UCC |

| EXTERIOR GAS PIPE BURIAL DEPTH | 18.0 inches depth | >= 12.0 inches | **PASS** | 2021 IFGC § 404.12 / PA UCC |

| GAS APPLIANCE SEDIMENT TRAP | Tee Trap Installed at Appliance | REQUIRED | **PASS** | 2021 IFGC § 408.4 / PA UCC |

| CSST GAS TUBING DIRECT BONDING | 6 AWG Bonding Jumper Installed | REQUIRED | **PASS** | 2021 IFGC § 310.1.1 / PA UCC |

| PA TEMPORARY OCCUPANCY PERMIT | Approved for Phased Occupancy | PERMITTED | **PASS** | 34 Pa. Code § 403.64 / PA UCC |

| PA UNINSPECTED COMMERCIAL EVALUATION | Structural & Fire Review Filed | REQUIRED | **PASS** | PA Act 95 of 2005 / PA UCC |

| GROUP E EDUCATIONAL CLASSIFICATION | Classified as Group E | CLASSIFIED | **PASS** | 2021 IBC § 305.2 / PA UCC |

| GROUP I-2 MEDICAL CARE CLASSIFICATION | Classified as Group I-2 | CLASSIFIED | **PASS** | 2021 IBC § 308.2 / PA UCC |

| ALLOWABLE BUILDING HEIGHT & AREA | Type II-A Construction Compliant | COMPLIANT | **PASS** | 2021 IBC Table 503 / PA UCC |

| STRUCTURAL FIRE WALL INDEPENDENCE | 2-Hour Double Fire Wall | REQUIRED | **PASS** | 2021 IBC § 706.4 / PA UCC |

| SHAFT ENCLOSURE FIRE RESISTANCE | 2-Hour Enclosure Assembly | REQUIRED | **PASS** | 2021 IBC § 707.3.1 / PA UCC |

| EXIT WALL FINISH FLAME SPREAD | Class A Finish Specified | Class A (0-25) | **PASS** | 2021 IBC Table 803.13 / PA UCC |

| COMMERCIAL RESIDENTIAL SPRINKLERS | NFPA 13R System Installed | REQUIRED | **PASS** | 2021 IBC § 903.2.8 / PA UCC |

| GROUP E MANUAL FIRE ALARM SYSTEM | Voice Evacuation Alarm System | REQUIRED | **PASS** | 2021 IBC § 907.2.3 / PA UCC |

| STRUCTURAL GROUND SNOW LOAD | 40.0 PSF (Scranton Region) | >= 35.0 PSF | **PASS** | 2021 IBC § 1608.2 / PA UCC |

| STRUCTURAL BASIC WIND SPEED | 115.0 MPH | >= 110.0 MPH | **PASS** | 2021 IBC § 1609.3 / PA UCC |

| MUNICIPAL FLOOD HAZARD ORDINANCE | Local Ordinance Compliance | REQUIRED | **PASS** | 2021 IBC § 1612.3 / PA UCC |

| ELEVATOR AMBULANCE STRETCHER SIZE | Cab Accommodates 24x84 Stretcher | REQUIRED | **PASS** | 2021 IBC § 3002.4 / 34 Pa. Code Ch. 405 |

| POOL ANTI-ENTRAPMENT SUCTION COVER | ANSI/APSP-16 Cover Specified | REQUIRED | **PASS** | 2021 ISPSC § 305.2 / PA UCC |

| PUBLIC POOL WATER TURNOVER RATE | 5.0 Hours Turnover | <= 6.0 Hours | **PASS** | 2021 ISPSC § 310.1 / PA UCC |

| WILDLAND-URBAN INTERFACE ROOF CLASS | Class A Roof Specified | REQUIRED | **PASS** | 2021 IWUIC § 504.5 / PA UCC |

| WUI CHIMNEY FLUE SPARK ARRESTER | 1/2-Inch Mesh Screen Installed | REQUIRED | **PASS** | 2021 IWUIC § 504.7 / PA UCC |

| PERFORMANCE-BASED DESIGN VALIDATION | PE Alternative Engineering Filed | REQUIRED | **PASS** | 2021 ICCPC § 301.1 / PA UCC |

> **Disclaimer:** This automated report is produced for decision-support QA and pre-check verification. It does not replace review by a licensed Architect or Professional Engineer.